



EPL 21807 Monitoring Report May 2025

SSMWSASSM-PLD-1NL-NL000-EV-RPT-000037

Parklife Metro D&C

Approval Record

Revision	Author	Date	Issue	Reviewed by	Approved by
00	[REDACTED]	5/06/2025	Initial Draft	[REDACTED]	[REDACTED]
Signature	[REDACTED]			[REDACTED]	[REDACTED]

Contents

1	Introduction.....	5
1.1	Background	5
1.1.1	Stations, Systems, Trains, Operations and Maintenance works	5
1.2	Scope of this report	7
2	Reporting requirements	8
3	Monitoring	16
3.1	Weather Monitoring	16
3.2	Noise and Vibration Monitoring.....	16
3.3	Water Monitoring	18
3.3.1	Surface water monitoring.....	18
3.3.2	Discharge to water.....	18
3.4	Correction Log	21
Appendix A	Weather Observations.....	23
Appendix B	Noise Monitoring.....	24
Appendix C	Discharge to water	26
Appendix D	Surface water monitoring.....	27
Appendix E	Premise Maps - May	28

Table of Figures

FIGURE 1 OVERVIEW OF SMWSA PROJECT	6
------------------------------------------	---

Table of Tables

TABLE 1 LICENCE DETAILS	7
TABLE 2 EPL 21807 MONITORING REQUIREMENTS	9
TABLE 3 WEATHER SUMMARY AND TRIGGER WEATHER EVENTS FOR REPORTING PERIOD	16
TABLE 4 SUMMARY OF NOISE MONITORING FOR REPORTING PERIOD	17
TABLE 5 MONITORING/DISCHARGE POINTS AND AREAS	19
TABLE 6 MONTHLY WEATHER OBSERVATION TABLE	23
TABLE 7 DETAILED NOISE MONITORING DATA.....	24
TABLE 8 WATER DISCHARGE TABLE	26

1 Introduction

1.1 Background

Sydney Metro is Australia's biggest public transport program comprising four main packages of work including Metro North-West Line, Sydney Metro City and Southwest, Sydney Metro West, and Sydney Metro Western Sydney Airport (SMWSA, the Project). The SMWSA will become the transport spine for Greater Western Sydney, connecting communities and travellers with the new Western Sydney International (Nancy-Bird Walton) Airport (referred to as Western Sydney International) and the growing region.

The Project involves the construction and operation of a new metro railway line around 23km in length that extends from the existing Sydney Trains suburban T1 Western Line at St Marys in the north to the new Bradfield Station in the south at Bringelly. The alignment includes a combination of tunnel, surface, bridges and viaduct sections, and comprises of six new metro stations between St Marys and the Bradfield Core precinct, as well as a stabling and maintenance facility and operational control centre to support the operation of the new metro railway line (see Figure 1).

1.1.1 Stations, Systems, Trains, Operations and Maintenance works

Parklife Metro D&C has been engaged to deliver the Stations, Systems, Trains, Operations and Maintenance (SSTOM) works. The scope of the Stations, Systems, Trains, Operations and Maintenance (SSTOM) package comprises:

- construction of the six new stations
- installation of tracks, signalling, mechanical and electrical systems
- supplying new driverless trains
- construction of stabling and maintenance facility at Orchard Hills
- operation and maintenance of the line and its assets, and
- handback of operations and maintenance at the end of term.




FIGURE 1 OVERVIEW OF SMWSA PROJECT

1.2 Scope of this report

Parklife Metro D&C have been issued an Environment Protection Licence (EPL No. 21807) from the NSW Environment Protection Authority (EPA) for the SMWSA SSTOM Works. The EPL applies to the works approved under the Infrastructure Approval SSI-10051 associated with the delivery of the off-airport portion of the SMWSA SSTOM Works, as detailed in Table 1. This EPL Monitoring Report provides the results of all pollution monitoring required to be measured or monitored by the licensee of EPL 21807 within the reporting period as required by Section 66 of the *Protection of the Environment Operations Act 1997* (POEO Act) and with reference to EPA Publication *Requirements for publishing pollution monitoring data* (Environment Protection Authority, 2013).

TABLE 1 LICENCE DETAILS

Licence Details	
Number	21807
Copy of Licence	Environment & Heritage POEO Licences, Application and Notice Detail (nsw.gov.au)
Anniversary Date	20-July
Licensee	WEBUILD S.P.A
Premises	SYDNEY METRO WESTERN SYDNEY AIRPORT SSTOM PACKAGE FOOTPRINT SYDNEY METRO WESTERN SYDNEY AIRPORT-STATIONS, SYSTEMS, TRAINS, OPERATION & MAINTENANCE PACKAGE
Scheduled Activity	Railway activities – railway infrastructure construction

2 Reporting requirements

Under the POEO Act, holders of environment protection licences (licensees) must publish or make pollution monitoring data available to members of the public.

The POEO Act Section 66 requires:

“Conditions requiring monitoring, certification or provision of information, and related offences

(1) Monitoring The conditions of a licence may require—

(a) monitoring by the holder of the licence of the activity or work authorised, required or controlled by the licence, including with respect to—

(i) the operation or maintenance of premises or plant, and

(ii) discharges from premises, and

(iii) relevant ambient conditions prevailing on or outside premises, and

(iv) anything required by the conditions of the licence, and

(b) the provision and maintenance of appropriate measuring and recording devices for the purposes of that monitoring, and

(c) the analysis, reporting and retention of monitoring data.

(2) False or misleading information A holder of a licence who supplies information, or on whose behalf information is supplied, to the appropriate regulatory authority under the conditions of the licence is guilty of an offence if the information is false or misleading in a material respect.”

The primary objective of the EPL Monitoring Report is that members of the public have access to the results of all pollution monitoring (which a licence specifies must be carried out) in a way that is meaningful to them.

The monitoring data that must be published and/or made available on request is any data that is obtained as a result of a monitoring condition on a licence that relates to air, water (surface or groundwater), noise and/or land pollution. The data to be published or provided is limited to data that relates to pollutants generated, discharged or emitted from the licensed premises.

The data is provided in tabular format that is easy for the general public to understand. Tables definitively display raw data values, while graphs and charts are useful for overviews and visualisation of long-term trends. Raw data will be provided upon request.

This EPL Monitoring Report will provide explanations as to why data may appear to be missing, which may be due to there being no discharge or the level of pollutant being below the detection level of the measurement instrument.

It's possible from time to time that incorrect data may get published in good faith. As soon as practicable after the licensee becomes aware that the published pollution monitoring data is incorrect or misleading, licensees must then publish a correction log to correct this data that is incorrect or misleading.

Table 2 provides a summary of the monitoring requirements of EPL 21807.

TABLE 2 EPL 21807 MONITORING REQUIREMENTS

EPL Condition	Requirement	Report Reference
Weather		
M5.1	<p>The licensee must monitor and record temperature, wind direction, wind velocity and rainfall at either the project weather station, or through analysis of equivalent weather information obtained from the Australian Bureau of Meteorology. Monitoring must:</p> <ul style="list-style-type: none"> a) be representative of the premises; b) commence prior to any works that may cause sediment to leave the premises; and c) continue to be operated until soil disturbance activities cease at the premises and the site has been stabilised. 	Section 3.1 Appendix A
Noise		
L5.9	<p>Works outside of standard construction hours – Regulatory Requirements</p> <p>In undertaking any works and activities outside of standard construction hours under condition L5.8, the licensee must comply with the following:</p> <ul style="list-style-type: none"> a) Prepare a construction noise and vibration impact assessment in accordance with the Interim Construction Noise Guideline (DEC, 2009) that is to include: <ul style="list-style-type: none"> i. a description of the proposed works and activities outside of standard construction hours; ii. predictions of LAeq (15 minute) dB noise levels at noise sensitive receivers from these works and activities, where noise levels are predicted to be greater than those permitted under condition L5.3; and iii. a monitoring plan to validate the noise predictions, based on monitoring at the boundary of representative sensitive receivers during noise generating activities that are representative of the works and activities, including during the period/s predicted to have the highest noise level impacts. b) Undertake noise monitoring in accordance with the monitoring plan required by condition L5.9(a)(iii). 	Section 3.2 Appendix B

L5.10	<p>St Marys Station, Orchard Hills Station and Bradfield Station - Out of Hours Concrete Works Concrete works associated with station box construction at St Marys Station, Orchard Hills Station and Bradfield Station, including concrete pouring, finishing and cleaning, are permitted to be undertaken outside of standard construction hours specified in L5.1 provided that:</p> <p>a) Works are required to achieve compliance with overarching project technical requirements,</p> <p>b) Works had already begun within a reasonable time prior to end of standard construction hours,</p> <p>c) Out of Hours (OOH) works are undertaken from 5am to 7am and 6pm to 12am (midnight), Monday to Friday and 6am to 8am and 1pm to 6pm on Saturday,</p> <p>d) Station box base slab and wall concreting activities and supporting formwork and reinforcement activities are permitted to occur up to 12am (midnight) Monday to Friday a total of 12 times per month until all base slabs and wall pours are completed,</p> <p>e) Station box base slab and wall concreting activities and supporting formwork and reinforcement activities (e.g. using concrete pump, vibrators, concrete trucks, etc) must be completed before 12am (midnight) on Monday to Friday,</p> <p>f) All other concreting activities (e.g. using concrete pump, vibrators, concrete trucks, etc) must be completed before 10pm on Monday to Friday,</p> <p>g) Concrete finishing works (e.g. power floats, hand tools) must be completed before 12am (midnight) on Monday to Friday,</p> <p>h) The licensee is required to undertake noise monitoring in accordance with condition L5.9(b),</p> <p>i) The licensee is required to undertake noise monitoring on a monthly basis at each Station and additionally monitor the first three instances of OOH concrete works at each Station:</p> <ol style="list-style-type: none"> 1. commencing prior to 7am, and 2. extending past 10pm <p>j) The licensee is required to provide the EPA with a Noise Monitoring Report within 30 days of the end of each month,</p> <p>k) Works are permitted to occur until 31 December 2025.</p>	Section 3.2 Appendix B
L5.11	<p>St Marys, Orchard Hills and Bradfield Station sites - Out of Hours Precast Concrete Beam Installation Installation Precast beam installation for station box construction at St Marys, Orchard Hills and Bradfield Station sites is permitted to be undertaken outside of standard construction hours specified in L5.1, provided that:</p> <p>a) Works are required to achieve compliance with project requirements for unloading oversize/overmass precast beam deliveries and site safety requirements,</p> <p>b) Works and activities are undertaken from 12am (midnight) to 7am, Monday to Friday nights,</p> <p>c) The licensee is required to undertake noise monitoring in accordance with condition L5.9(b),</p> <p>d) The licensee is required to undertake noise monitoring at each Station on a monthly basis, and additionally monitor:</p> <ol style="list-style-type: none"> 1. the first two instances of OOH concrete beam installation at each Station, and 2. the first two instances of OOH concrete beam installation at each Station that occurs concurrently with activities permitted under Condition L5.10. <p>e) The licensee is required to provide the EPA with a Noise Monitoring Report within 30 days of the end of each month,</p> <p>f) Works are permitted to occur until 31 May 2025.</p>	Section 3.2 Appendix B

L5.12	<p>Stabling and Maintenance Facility - Out of Hours Concrete Works Concrete works associated with Maintenance & Administration and Operational Control Centre buildings at the Stabling and Maintenance Facility, including concrete pouring, finishing, and cleaning, are permitted to be undertaken outside of standard construction hours specified in L5.1 provided that:</p> <p>a) Works are required to achieve compliance with overarching project technical requirements,</p> <p>b) Works had already begun within a reasonable time prior to end of standard construction hours,</p> <p>c) Out of Hours works (OOH) are undertaken from 5am to 7am and 6pm to 12am (midnight), Monday to Friday, and 6am to 8am, and 1pm - 6pm on Saturday,</p> <p>d) Base slab concreting activities and supporting formwork and reinforcement activities must be completed before 12am (midnight) Monday to Friday,</p> <p>e) Base slab concreting activities and supporting formwork and reinforcement activities are permitted to occur up to 12am (midnight) Monday to Friday a total of 12 times per month until base slabs are completed,</p> <p>f) All other concreting activities (e.g. using concrete pump, vibrators, concrete trucks, etc) must be completed before 10pm on Monday to Friday,</p> <p>g) Concrete finishing works (e.g. power floats, hand tools) must be completed before 12am (midnight) on Monday to Friday,</p> <p>h) The licensee is required to undertake noise monitoring in accordance with L5.9(b),</p> <p>i) The licensee is required to undertake noise monitoring on a monthly basis and additionally during the first three instances of OOH concrete works:</p> <ol style="list-style-type: none"> 1. commencing prior to 7am, and 2. extending past 10pm. <p>j) The licensee is required to provide the EPA with a Noise Monitoring Report within 30 days of the end of each month,</p> <p>k) Works are permitted to occur until 31 July 2025.</p>	Section 3.2 Appendix B
L5.13	<p>Orchard Hills Station site - Out of Hours Concrete Batch Plant Operation The concrete batch plant located at the Orchard Hills site is permitted to operate outside of standard construction hours specified in L5.1 provided that:</p> <p>a) Operation of the plant is required to achieve compliance with overarching project technical requirements of large concrete pours permitted by condition L5.10 and L5.12</p> <p>b) Concrete works had already begun within a reasonable time prior to end of standard construction hours,</p> <p>c) Out of Hours (OOH) works are undertaken from 5am to 7am and 6pm to 10pm Monday to Friday, and 6am to 8am and 1pm to 6pm on Saturday,</p> <p>d) The licensee is required to undertake noise monitoring in accordance with condition L5.9(b),</p> <p>e) The licensee is required to undertake noise monitoring on a monthly basis and additionally monitor the first three instances of OOH operation of the concrete batch plant:</p> <ol style="list-style-type: none"> 1. commencing prior to 7am, and 2. extending past 8pm <p>f) The licensee is required to provide the EPA with a Noise Monitoring Report within 30 days of the end of each month,</p> <p>g) Works are permitted to occur until 31 July 2025.</p>	Section 3.2 Appendix B

L5.14	<p>Works outside standard construction hours - 24-hour works</p> <p>a) The following works are permitted to be undertaken 24 hours a day, 7 days per week for activities at the St Marys Station Site, Claremont Meadows services shaft site, Orchard Hills Station site, Bringelly services shaft site, and Bradfield Station site:</p> <ul style="list-style-type: none"> i. Tunnel and underground station box fit out works and ancillary surface support works ii. Haulage and delivery of materials to the Claremont Meadows services shaft site and Bringelly services shaft site. <p>b) The licensee is required to undertake attended noise monitoring:</p> <ul style="list-style-type: none"> 1. on the first two occasions of 24-hour works at each site: <ul style="list-style-type: none"> i. St Marys Station site, ii. Claremont Meadows services shaft site, iii. Orchard Hills Station site, iv. Bringelly services shaft site, v. Bradfield Station site, and 2. noise monitoring must occur in the night time period. 3. the licensee is required to provide the EPA with a Noise Monitoring Report within 30 days of the end of the month in which noise monitoring was undertaken. 	
M4.4	<p>The licensee must undertake noise and vibration monitoring as directed by an authorised officer of the EPA. Where the monitoring is requested to take place on private land (for example a residential property) the licensee must request permission to access the premises in advance and keep a record of permission requests and responses. If a licensee is unable to obtain permission, the licensee must undertake the monitoring at an indicative location where possible and they must provide the response (including any nil response) to the EPA.</p>	Not triggered
<p>Community Agreements</p> <p>The licensee may work outside standard construction hours (as defined in L5.1) in circumstances other than those permitted under conditions L5.3, L5.4, or any other condition of the licence, subject to the condition outlined Section E1.</p>		
E1.4	<p>A noise validation monitoring plan must be submitted to the EPA for approval as part of the community agreement documentation prior to any OOHW occurring.</p>	Section 3.2 Appendix B
E1.5	<p>Validation monitoring must be undertaken for any OOHW that are the approved under condition E1.1 and must:</p> <ul style="list-style-type: none"> a) be undertaken in accordance with the monitoring plan prepared under condition E1.4; b) be performed by a Competent Person; c) be performed on at least the first 2 occasions (day, evening, nights) where OOHW will be undertaken and are likely to impact Noise Sensitive Receivers; d) be performed on any other occasion (day, evening, night) where the nature of the works is likely to cause greater noise impacts than the first 2 occasions; e) be representative of the impacts in terms of monitoring locations, time and duration of measurements; and f) be recorded and provided to an EPA officer upon request. 	Section 3.2 Appendix B
<p>Water</p>		

P1.1

The following points referred to in the table are identified in this licence for the purposes of the monitoring and/or the setting of limits for discharges of pollutants to water from the point.

Section
3.3.2
Table 5

EPA Identification no	Type of Monitoring Point	Type of Discharge Point	Location Description
1	Discharge and Monitoring	Discharge and Monitoring	The outlet of the sediment basin on the Bradfield site discharging to Thompson Creek referred to in Condition P1.2
2	Discharge and Monitoring	Discharge and Monitoring	The outlet of the water treatment plant on the St Marys site discharging to South Creek
3	Discharge and Monitoring	Discharge and Monitoring	The outlet of the sediment basin on the Orchard Hills site discharging to an Unnamed Creek (tributary of South Creek) referred to in Condition P1.2
4	Discharge and Monitoring	Discharge and Monitoring	The outlet of the water treatment plant on the Bradfield site discharging to Thompson Creek
5	Discharge and Monitoring	Discharge and Monitoring	The outlet of the sediment basin at the Stabling and Maintenance Facility site discharging to Blaxland Creek referred to in Condition P1.2
6	Discharge and Monitoring	Discharge and Monitoring	The outlet of the sediment basin discharging to Cosgroves Creek referred to in Condition P1.2
7	Discharge and Monitoring	Discharge and Monitoring	The outlet of the sediment basin on Orchard Hills site discharging to South Creek referred to in Condition P1.2
8	Discharge and Monitoring	Discharge and Monitoring	The outlet of the sediment basin near Elizabeth Drive discharging to Badgerys Creek referred to in Condition P1.2
9	Discharge and Monitoring	Discharge and Monitoring	The outlet of the sediment basin at the Claremont Meadows site discharging to local stormwater referred to in Condition P1.2.
10	Discharge and Monitoring	Discharge and Monitoring	The outlet of the sediment basin at the Claremont Meadows site discharging to local stormwater referred to in Condition P1.2.
11	Discharge and Monitoring	Discharge and Monitoring	The outlet of the sediment basin discharging to an unnamed tributary of Blaxland Creek referred to in Condition P1.2.
12	Discharge and Monitoring	Discharge and Monitoring	The outlet of the sediment basin on the Stabling and Maintenance Facility site discharging to Blaxland Creek referred to in Condition P1.2
13	Discharge and Monitoring	Discharge and Monitoring	The outlet of the sediment basin located south of Patons Lane discharging to an unnamed tributary of South Creek referred to in Condition P1.2
14	Discharge and Monitoring	Discharge and Monitoring	The outlet of the sediment basin at the Bringelly site discharging to Badgerys Creek referred to in Condition P1.2.
15	Discharge and Monitoring	Discharge and Monitoring	The outlet of the sediment basin near Luddenham Station

			discharging to an unnamed tributary of South Creek referred to in Condition P1.2																																																																																																																	
M2.2	<p>Water and/or Land Monitoring Requirements POINT 1, 3, 5, 6, 7, 8, 9, 10, 11, 12, 13, 14, 15</p> <table border="1"> <thead> <tr> <th>Pollutant</th> <th>Unit of measure</th> <th>Frequency</th> <th>Sampling Method</th> </tr> </thead> <tbody> <tr> <td>Oil and Grease</td> <td>Visible</td> <td>Special Frequency 1</td> <td>Visual inspection</td> </tr> <tr> <td>pH</td> <td>pH</td> <td>Special Frequency 1</td> <td>Probe</td> </tr> <tr> <td>Turbidity</td> <td>nephelometric turbidity units</td> <td>Special Frequency 1</td> <td>Probe</td> </tr> </tbody> </table> <p>POINT 2</p> <table border="1"> <thead> <tr> <th>Pollutant</th> <th>Units of measure</th> <th>Frequency</th> <th>Sampling Method</th> </tr> </thead> <tbody> <tr> <td>Aluminium</td> <td>milligrams per litre</td> <td>Daily during any Grab sample discharge</td> <td>Grab sample</td> </tr> <tr> <td>Ammonia</td> <td>milligrams per litre</td> <td>Daily during any Grab sample discharge</td> <td>Grab sample</td> </tr> <tr> <td>Chromium (VI) Compounds</td> <td>milligrams per litre</td> <td>Daily during any discharge</td> <td>Grab sample</td> </tr> <tr> <td>Copper</td> <td>milligrams per litre</td> <td>Daily during any discharge</td> <td>Grab sample</td> </tr> <tr> <td>Electrical conductivity</td> <td>microsiemens per centimetre</td> <td>Daily during any discharge</td> <td>Grab sample</td> </tr> <tr> <td>Nitrogen (total)</td> <td>milligrams per litre</td> <td>Daily during any discharge</td> <td>Grab sample discharge</td> </tr> <tr> <td>Oil and Grease</td> <td>Visible</td> <td>Daily during any discharge</td> <td>Visual Inspection</td> </tr> <tr> <td>pH</td> <td>pH</td> <td>Daily during any discharge</td> <td>Probe</td> </tr> <tr> <td>Phosphorus (total)</td> <td>milligrams per litre</td> <td>Daily during any discharge</td> <td>Grab sample</td> </tr> <tr> <td>TSS</td> <td>milligrams per litre</td> <td>Daily during any discharge</td> <td>Grab sample</td> </tr> <tr> <td>Zinc</td> <td>milligrams per litre</td> <td>Daily during any discharge</td> <td>Grab sample</td> </tr> </tbody> </table> <p>POINT 4</p> <table border="1"> <thead> <tr> <th>Pollutant</th> <th>Units of measure</th> <th>Frequency</th> <th>Sampling Method</th> </tr> </thead> <tbody> <tr> <td>Aluminium</td> <td>milligrams per litre</td> <td>Monthly during discharge</td> <td>Grab sample</td> </tr> <tr> <td>Ammonia</td> <td>milligrams per litre</td> <td>Monthly during discharge</td> <td>Grab sample</td> </tr> <tr> <td>Chromium (VI) Compounds</td> <td>milligrams per litre</td> <td>Monthly during discharge</td> <td>Grab sample</td> </tr> <tr> <td>Copper</td> <td>milligrams per litre</td> <td>Monthly during discharge</td> <td>Grab sample</td> </tr> <tr> <td>Electrical conductivity</td> <td>microsiemens per centimetre</td> <td>Monthly during discharge</td> <td>Grab sample</td> </tr> <tr> <td>Nitrogen (total)</td> <td>milligrams per litre</td> <td>Monthly during discharge</td> <td>Grab sample</td> </tr> <tr> <td>Oil and Grease</td> <td>Visible</td> <td>Monthly during discharge</td> <td>Visual Inspection</td> </tr> <tr> <td>pH</td> <td>pH</td> <td>Monthly during discharge</td> <td>Probe</td> </tr> <tr> <td>Phosphorus (total)</td> <td>milligrams per litre</td> <td>Monthly during discharge</td> <td>Grab sample</td> </tr> <tr> <td>TSS</td> <td>milligrams per litre</td> <td>Monthly during discharge</td> <td>Grab sample</td> </tr> <tr> <td>Zinc</td> <td>milligrams per litre</td> <td>Monthly during discharge</td> <td>Grab sample</td> </tr> </tbody> </table>			Pollutant	Unit of measure	Frequency	Sampling Method	Oil and Grease	Visible	Special Frequency 1	Visual inspection	pH	pH	Special Frequency 1	Probe	Turbidity	nephelometric turbidity units	Special Frequency 1	Probe	Pollutant	Units of measure	Frequency	Sampling Method	Aluminium	milligrams per litre	Daily during any Grab sample discharge	Grab sample	Ammonia	milligrams per litre	Daily during any Grab sample discharge	Grab sample	Chromium (VI) Compounds	milligrams per litre	Daily during any discharge	Grab sample	Copper	milligrams per litre	Daily during any discharge	Grab sample	Electrical conductivity	microsiemens per centimetre	Daily during any discharge	Grab sample	Nitrogen (total)	milligrams per litre	Daily during any discharge	Grab sample discharge	Oil and Grease	Visible	Daily during any discharge	Visual Inspection	pH	pH	Daily during any discharge	Probe	Phosphorus (total)	milligrams per litre	Daily during any discharge	Grab sample	TSS	milligrams per litre	Daily during any discharge	Grab sample	Zinc	milligrams per litre	Daily during any discharge	Grab sample	Pollutant	Units of measure	Frequency	Sampling Method	Aluminium	milligrams per litre	Monthly during discharge	Grab sample	Ammonia	milligrams per litre	Monthly during discharge	Grab sample	Chromium (VI) Compounds	milligrams per litre	Monthly during discharge	Grab sample	Copper	milligrams per litre	Monthly during discharge	Grab sample	Electrical conductivity	microsiemens per centimetre	Monthly during discharge	Grab sample	Nitrogen (total)	milligrams per litre	Monthly during discharge	Grab sample	Oil and Grease	Visible	Monthly during discharge	Visual Inspection	pH	pH	Monthly during discharge	Probe	Phosphorus (total)	milligrams per litre	Monthly during discharge	Grab sample	TSS	milligrams per litre	Monthly during discharge	Grab sample	Zinc	milligrams per litre	Monthly during discharge	Grab sample	<p>Section 3.3.2 Appendix C</p>
Pollutant	Unit of measure	Frequency	Sampling Method																																																																																																																	
Oil and Grease	Visible	Special Frequency 1	Visual inspection																																																																																																																	
pH	pH	Special Frequency 1	Probe																																																																																																																	
Turbidity	nephelometric turbidity units	Special Frequency 1	Probe																																																																																																																	
Pollutant	Units of measure	Frequency	Sampling Method																																																																																																																	
Aluminium	milligrams per litre	Daily during any Grab sample discharge	Grab sample																																																																																																																	
Ammonia	milligrams per litre	Daily during any Grab sample discharge	Grab sample																																																																																																																	
Chromium (VI) Compounds	milligrams per litre	Daily during any discharge	Grab sample																																																																																																																	
Copper	milligrams per litre	Daily during any discharge	Grab sample																																																																																																																	
Electrical conductivity	microsiemens per centimetre	Daily during any discharge	Grab sample																																																																																																																	
Nitrogen (total)	milligrams per litre	Daily during any discharge	Grab sample discharge																																																																																																																	
Oil and Grease	Visible	Daily during any discharge	Visual Inspection																																																																																																																	
pH	pH	Daily during any discharge	Probe																																																																																																																	
Phosphorus (total)	milligrams per litre	Daily during any discharge	Grab sample																																																																																																																	
TSS	milligrams per litre	Daily during any discharge	Grab sample																																																																																																																	
Zinc	milligrams per litre	Daily during any discharge	Grab sample																																																																																																																	
Pollutant	Units of measure	Frequency	Sampling Method																																																																																																																	
Aluminium	milligrams per litre	Monthly during discharge	Grab sample																																																																																																																	
Ammonia	milligrams per litre	Monthly during discharge	Grab sample																																																																																																																	
Chromium (VI) Compounds	milligrams per litre	Monthly during discharge	Grab sample																																																																																																																	
Copper	milligrams per litre	Monthly during discharge	Grab sample																																																																																																																	
Electrical conductivity	microsiemens per centimetre	Monthly during discharge	Grab sample																																																																																																																	
Nitrogen (total)	milligrams per litre	Monthly during discharge	Grab sample																																																																																																																	
Oil and Grease	Visible	Monthly during discharge	Visual Inspection																																																																																																																	
pH	pH	Monthly during discharge	Probe																																																																																																																	
Phosphorus (total)	milligrams per litre	Monthly during discharge	Grab sample																																																																																																																	
TSS	milligrams per litre	Monthly during discharge	Grab sample																																																																																																																	
Zinc	milligrams per litre	Monthly during discharge	Grab sample																																																																																																																	
M2.3	<p>For the purposes of Condition M2.2 and the Table thereto, 'Special Frequency 1' means:</p> <p>a) less than 24 hours prior to a controlled discharge and daily for any continued controlled discharge, when it is safe to do so; and</p> <p>b) when rainfall causes a discharge from a sediment basin which has not been emptied within the design management period following cessation of a rainfall event, when it is safe to do so.</p>			<p>Section 3.3.2</p>																																																																																																																

E2.1	<p>The licensee must undertake surface water monitoring of receiving waterways at locations upstream, downstream and adjacent to discharge points 2 and 4 identified in Condition P1.1 at fortnightly intervals and at least once during each discharge event. This monitoring must be undertaken for a minimum of 3 months:</p> <p>a) from the date that point 2 was added to the licence; and</p> <p>b) from the date that discharge from point 4 commences.</p> <p>Surface water monitoring results must include:</p> <p>a) quality and quantity of all parameters that are identified in the table in M2.2 for discharge points 2 and 4; and</p> <p>b) results must be submitted to the EPA no more than 2 weeks after each monitoring event has occurred for a minimum of 3 months:</p> <p>i. from the date that point 2 was added to the licence; and</p> <p>ii. from the date that discharge from point 4 commences.</p>	Section 3.3.1
E3.1	<p>Water Treatment Plant (WTP) Performance Reporting</p> <p>A) The licensee must undertake water quality sampling of all discharges from the WTP (as identified as Point 2 and 4 under condition P1.1) and submit to the EPA a WTP Performance Report within 10 business days of each sample result being taken. Sampling must be undertaken:</p> <p>i) daily during discharge</p> <p>ii) as per condition M2.2, following this sampling frequency or as directed by the EPA.</p>	Not Triggered
Additional Monitoring Conditions		
M4.5	<p>The licensee must undertake monitoring, sampling, video recording and/or take photographs:</p> <p>a) if the EPA or licensee reasonably suspects that an event has occurred at the premises or in connection with the carrying out of the activities that has caused, is causing, is likely to cause or has the potential to cause material harm to the environment (whether the harm occurs on or off premises to which the licence applies);</p> <p>b) as soon as practicable; and</p> <p>c) as directed by an authorised officer.</p>	Not triggered

3 Monitoring

This section presents summaries of the monitoring completed in the reporting period from 1 May 2025 to 31 May 2025.

Detailed monitoring results for each program are presented in the Appendices.

3.1 Weather Monitoring

Meteorological observations were captured using the Bureau of Meteorology Weather Stations - Badgerys Creek (Station 067108). Meteorological data for the month of May can be found within Appendix A.

The total rainfall for this reporting period was 98.2mm with 7 days exceeding 1mm of rain, 2 days exceeding 10mm of rain and 1 days exceeding 20mm of rain.

During the reporting period, 10 days recorded wind gusts of greater than 25km/hr, 1 day where the maximum wind gust recorded was greater than 50 km/h and 1 day where the maximum wind gust was greater than 60 km/hr. Detailed weather observation records for the reporting period are presented in Appendix A.

This information is used daily on site to assess daily activities and consider mitigation measures as required.

TABLE 3 WEATHER SUMMARY AND TRIGGER WEATHER EVENTS FOR REPORTING PERIOD

Weather Event	Observation
Minimum temperature (°C)	0
Maximum temperature (°C)	73.6
Total rainfall (mm)	98.2
Number of days with rain (>1mm)	7
Number of days with rain (>10mm)	2
Number of days with rain (>20mm)	1
Number of days with >25km/h wind gust	10
Number of days with >50km/h wind gust	1
Number of days with >60km/h wind gust	1

3.2 Noise and Vibration Monitoring

Noise monitoring is required under Conditions L5.9, L5.10, L5.11, L5.12, L5.13, L5.14 and E1.5 to validate noise predications for work undertaken outside of standard construction hours in accordance with the construction noise and vibration assessment and monitoring plan. All noise monitoring performed under EPL (21807) will be included in Appendix B.

TABLE 4 SUMMARY OF NOISE MONITORING FOR REPORTING PERIOD

Date	Monitoring Location	Attended / Continuous	Description
7/05/2025	40 Lansdowne Rd, Orchard Hills	Attended	Residence located on a busy intersection.
7/05/2025	3 Station Street, St Marys	Attended	Residence directly opposite St Marys Station.
15/05/2025	2 Station Street, St Marys	Attended	Residence directly opposite St Marys Station.
20/05/2025	9 Bordeaux Pl, Orchard Hills	Attended	Quiet residential area west of the Stabling and Maintenance Facility.
20/05/2025	372 Luddenham Rd, Luddenham	Attended	Residence located on a busy Road.
21/05/2025	62 Doncaster Avenue, Claremont Meadows	Attended	Residence located in a quiet neighbourhood, near the M4 highway.
21/05/2025	25 The Retreat, Bringelly	Attended	Residence located in a quiet neighbourhood.
23/05/2025	9 Bordeaux Place, Orchard Hills	Attended	Quiet residential area west of the Stabling and Maintenance Facility.
23/05/2025	40 Lansdowne Road, Orchard Hills	Attended	Residence located on a busy intersection.
27/05/2025	38 Derwent Road, Bradfield	Attended	Residence located on a quiet street.
27/05/2025	9 Bordeaux Place, Orchard Hills	Attended	Quiet residential area west of the Stabling and Maintenance Facility.
29/05/2025	38 Derwent Road, Bradfield	Attended	Residence on a quiet street south of Bringelly Shaft Facility.
29/05/2025	2 Putland Street, Claremont Meadows	Attended	Residence near a busy road.
29/05/2025	4 Dolphin Close, Claremont Meadows	Attended	Residence located in a quiet neighbourhood near busy roads.

3.3 Water Monitoring

3.3.1 Surface water monitoring

As per Condition E2.1 fortnightly sampling is required for at least 3 months from the date Point 2 was added to the licence (30 November 2023). This period ended on 30 February, and additional background monitoring was obtained through March and April. This monitoring is now complete.

Additionally, as per Condition E2.1 surface water monitoring will be conducted at discharge Point 4 at fortnightly intervals and at least once during each discharge event for a minimum of 3 months from the date that discharge from Point 4 commences. These water monitoring results will be presented in Appendix D accordingly.

3.3.2 Discharge to water

The discharge of water from sediment basins occurred at the following discharging monitoring points/locations during this reporting period:

- SSTOM-001
- SSTOM-014

The EPL discharge criteria apply to the sediment basins identified in condition L2.4 of the approved EPL 21807.

Basins and discharge points are summarised in Table 5. All monitoring results for May are included in Appendix C.

TABLE 5 MONITORING/DISCHARGE POINTS AND AREAS

ID	Construction Status	EPA ID	Easting	Northing	Description of location of discharge point	Catchment name	Name of nearest waters	Direct discharge to waters	Date added to EPL
SSTOM-001	Active	1	290807.84	6243844.20	The outlet of the sediment basin on the Bradfield site discharging to Thompson Creek	South Creek	Thompsons Creek	No	14/11/2023
SSTOM-002	Not active	2	294041.62	6261905.98	The outlet of the water treatment plant on the St Marys site at former Plaza	South Creek	South Creek	No	15/12/2023
SSTOM-003	Not active	3	291819.86	6258565.85	The outlet of the sediment basin on the Orchard Hills site discharging to an Unnamed Creek (tributary of South Creek)	South Creek	Blaxland Creek	No	14/02/2024
SSTOM-004	Not active	4	291447.72	6243909.96	The outlet of the water treatment plant on the Bradfield site discharging to Thompson Creek	South Creek	Thompsons Creek	Yes	15/05/2024
SSTOM-005	Not active	5	292112.47	6257621.18	The outlet of the sediment basin at the Stabling and Maintenance Facility site discharging to Blaxland Creek	South Creek	Blaxland Creek	No	28/08/2024
SSTOM-006	Not active	6	291092.66	6252180.95	The outlet of the sediment basin discharging to Cosgroves Creek	South Creek	Cosgrove Creek	No	04/09/2024
SSTOM-007	Not active	7	292065.7	6259303.9	The outlet of the sediment basin discharging to South Creek	South Creek	South Creek	No	15/11/2024
SSTOM-008	Not active	8	291981.6	6249912.7	The outlet of the sediment basin discharging to Badgerys Creek	Badgerys Creek	Badgerys Creek	No	4/12/2024
SSTOM-009	Not active	9	291981.6	6249912.7	The outlet of the sediment basin discharging to Claremont Creek	South Creek	Claremont Creek	No	16/01/2025
SSTOM-010	Not active	10	292018.2	6261255.3	The outlet of the sediment basin discharging to Claremont Creek	South Creek	Claremont Creek	No	16/01/2025

SSTOM-011	Not active	11	291965.4	6258444.4	The outlet of the sediment basin discharging to Badgerys Creek	South Creek	Badgerys Creek	Yes	16/01/2025
SSTOM-012	Not active	12	291985.4	6257951.5	The outlet of the sediment basin discharging to Badgerys Creek	South Creek	Badgerys Creek	No	16/01/2025
SSTOM-013	Not Active	13	291528.1	6255484.1	The outlet of the sediment basin located south of Patons Lane to Unnamed Creek	South Creek	Unnamed Creek	No	23/01/2025
SSTOM-014	Active	14	289482.8	6245852.0	The outlet of the sediment basin at the Bringelly site discharging to Badgerys Creek.	South Creek	Badgerys Creek	No	23/01/2025
SSTOM-015	Not active	15	290913.5	6253487.3	The outlet of the sediment basin near Luddenham Station discharging to an unnamed tributary of South Creek	South Creek	South Creek	No	25/03/2025

3.4 Correction Log

It is possible from time to time for incorrect data to get published in good faith.

As soon as practicable after the licensee becomes aware that the published pollution monitoring data is incorrect or misleading, licensees must then publish a correction log to correct this data that is incorrect or misleading.

There are no matters included in the correction log for this reporting period.

Appendices

Appendix A Weather Observations

TABLE 6 MONTHLY WEATHER OBSERVATION TABLE

Date	Temperature		Rainfall In the 24 hours to 9am (mm)	Wind Observations			Morning (9am) Weather Observation					Afternoon (3pm) Weather Observation				
	Minimum (°C)	Maximum (°C)		Direction of maximum wind gust	Speed of maximum wind gust (km/h)	Time of maximum wind gust	Temperature (°C)	9am relative humidity (%)	Wind direction	Wind speed (km/h)	9am MSL pressure (hPa)	Temperature (°C)	9am relative humidity (%)	Wind direction	Wind speed (km/h)	3pm MSL pressure (hPa)
1/05/2025	11.5	20.1	1.2	SW	41	10:35	15.5	66	SW	24	1028.4	17.3	53	S	19	1027.6
2/05/2025	9.9	20.8	0.2	SW	33	11:20	17.9	65	SSW	13	1033.3	19.4	62	SSE	13	1031.3
3/05/2025	10.1	23.1	0	SE	20	15:06	15.9	78	SW	13	1035.4	21.6	53	ENE	9	1032.8
4/05/2025	7.7	23	0	NNE	28	15:34	14.5	87		Calm	1034.8	22.1	53	NE	17	1030.9
5/05/2025	10.8	24.8	0	NNE	24	11:07	15.2	100	WNW	2	1030.7	22.6	57	NNE	9	1025.2
6/05/2025	10.3	25.3	0	NNE	15	15:04	15.8	100		Calm	1024.9	23.9	60	N	6	1020.3
7/05/2025	10.7	27.2	0	WNW	30	14:20	19	70	N	6	1019.5	26.9	43	N	7	1015.5
8/05/2025	10.2	22.1	0	WSW	28	1:22	17.6	55	S	9	1024.8	19.5	56	ESE	13	1025
9/05/2025	8.5	21.2	0	ENE	19	15:08	15.4	66	SW	9	1033.1	16.9	72	E	7	1030.6
10/05/2025	8.7	23.3	0	E	20	15:58	15.4	88	SW	7	1033.1	20.1	58	ESE	7	1029.5
11/05/2025	10.6	22.4	0.2	W	15	20:16	15.4	97	WNW	6	1030.8	17.6	86		Calm	1027.7
12/05/2025	15.3	23.8	4	E	17	15:46	19.4	90	W	2	1027.8	22.5	64	ENE	2	1024.6
13/05/2025	13.9	23.4	0	ESE	19	14:30	17.4	100	SW	4	1026.8	21.7	68	NE	4	1024.7
14/05/2025	10.2	23.9	0	NW	13	16:34	15.9	100	E	4	1021.9	22.4	60	ESE	2	1018.9
15/05/2025	11.7	21.4	0	S	22	11:49	17.2	82	SW	11	1022.3	19.3	73	SE	9	1020.4
16/05/2025	14.4	21.8	1.8	ESE	20	15:58	17.5	86	SW	9	1019.2	18.8	79	ESE	9	1015.3
17/05/2025	8.9	23.9	0.2	ESE	22	15:02	14.5	100		Calm	1016.5	21.6	57	S	9	1013.7
18/05/2025	13.2	16.4	0	SSW	46	16:36	15.4	65	SSW	15	1022.6	15.4	60	SSW	17	1022.2
19/05/2025	11.5	18.1	0.4	S	44	15:38	13.6	70	SW	15	1028.8	15.9	60	S	22	1028.4
20/05/2025	11.1	19.6	0.8	S	33	10:51	14.2	84	SSW	13	1030.9	17.3	63	SSE	9	1028.1
21/05/2025	12.7	18.3	1.4	SW	22	9:28	15.3	100	SW	11	1027.9	17.8	86	SSW	7	1025.3
22/05/2025	15	18.8	10.8	E	35	18:41	16.6	100	S	7	1019.9	17.6	100	SSE	9	1016.3
23/05/2025	16.3	22.6	73.6	E	31	0:29	17.6	100	ENE	11	1015.2	20.2	90	ESE	4	1010.6
24/05/2025	9.1	21.1	1	WNW	41	11:59	19.6	69	NW	6	1016	20.8	49	WNW	15	1013.2
25/05/2025	8.2	19.2	0	NNW	22	0:33	13.2	86	NNW	4	1019.6	16.8	64	SSE	4	1018.2
26/05/2025	6.3	16.5	0	NE	33	22:08	7.7	99		Calm	1019.7	14.2	74	NNW	4	1014.9
27/05/2025	10.5	17.9	2.4	WNW	69	15:05	13.7	83	NW	11	1009.2	14.8	53	W	20	1007.6
28/05/2025	7.4	19.9	0	WSW	46	1:53	14.3	62	NNE	6	1015.6	19.4	44	WSW	13	1013.8
29/05/2025	9.1	18.1	0.2	WSW	33	10:16	12.3	66	WSW	15	1019.7	17.1	61	WSW	15	1019.7
30/05/2025	4.7	21.1	0	WSW	17	9:34	11.7	87	SW	11	1025.3	20.4	51	E	4	1024.6
31/05/2025	7.1	21.2	0	W	15	11:11	12.8	91	WSW	6	1029.5	20.4	53	N	2	1027.3

Appendix B Noise Monitoring

TABLE 7 DETAILED NOISE MONITORING DATA

Date	Time	Construction Activity	Activity Location	Monitoring Location	NML (dBA)	Predicted (dBA)	Recorded LA _{eq(15min)} (dBA)	L _{Amax}	LA ₁₀	LA ₉₀	Exceedance of Predicted (dBA)	Exceedance of Predicted	Comments
7/05/2025	5:24	Batch Plant Operations	Orchard Hills	40 Lansdowne Rd, Orchard Hills	45	45	58.8	82.2	57.9	52.3	13.8	Yes	Dominant noise source attributed to traffic along M4, Lansdowne and Kent Rds. Compliant.
7/05/2025	6:06	Concrete pouring and supporting formwork	St Marys	3 Station Street, St Marys	41	59	61.5	83.6	60.3	50.4	2.5	Yes	Traffic was the dominant noise source. Compliant.
15/05/2025	00:12	Precast beam installation	St Marys	2 Station Street, St Marys	41	59	57.5	70.9	61.4	54.4	-1.5	No	The noise levels recorded during the beam lift operations were in compliance with the DNVIS predicted noise levels.
20/05/2025	21:43	Combined service route	Stabling and Maintenance Facility	9 Bordeaux Pl, Orchard Hills	45	55	38.9	51.2	40	37.3	-16.1	No	The noise levels recorded during work were in compliance with the DNVIS predicted noise levels.
20/05/2025	22:54	Formwork installation	Linewide North	372 Luddenham Rd, Luddenham	39	58	35.3	51.9	36.5	33.3	-22.7	No	Dominant noise source attributed to traffic in the distance from Luddenham Rd. PLM works not audible. Compliant.
21/05/2025	22:34	Tunnel and underground station box fit out works and ancillary surface support	Orchard Hills	62 Doncaster Avenue, Claremont Meadows	36	43	49	68.7	47.3	42.6	6	Yes	PLM Construction activities not audible from monitoring location. The dominant noise source was attributed to traffic from M4 and Doncaster Avenue. PLM works compliant.
21/05/2025	18:26	Concrete Pour	Bradfield	25 The Retreat, Bringelly	40	44	41.4	68.4	42.2	38.2	-2.6	No	PLM work was audible but did not exceed predicted noise levels. Compliant.

23/05/2025	22:30	Supporting formworks	Linewide North	9 Bordeaux Place, Orchard Hills	45	55	44.1	56.1	44.8	43.2	-10.9	No	PLM construction noise was faintly audible and included occasional mobile crane revs and hand tool operations. Frogs and insects were audible throughout and distant traffic noise contributed. Construction noise was measured below DNVIS prediction. Compliant
23/05/2025	23:07	Rail pulling into tunnel	Orchard Hills	40 Lansdowne Road, Orchard Hills	45	45	49.4	66.7	50.6	44.4	4.4	Yes	Cars passing on Lansdowne Road were the dominant noise source. PLM work was audible but did not exceed predicted noise levels. Compliant.
27/05/2025	22:00	Ventilation fans	Bringelly Shaft Facility	38 Derwent Road, Bradfield	39	49	47.7	53	48	46	-1.3	No	PLM work was audible but did not exceed predicted noise levels. Compliant.
27/05/2025	23:05	Supporting formworks + Combined service route	Linewide/Stabling and Maintenance Facility	9 Bordeaux Place, Orchard Hills	45	50	47	63	47	48	3	No	PLM work was audible but did not exceed predicted noise levels. Compliant.
29/05/2025	6:13	Ventilation fans	Bringelly Shaft Facility	38 Derwent Road, Bradfield	39	49	48.7	71.2	47.6	45.8	-0.3	No	Works were audible however just within the predicted noise levels. No other works were audible apart from the ventilation fans. Works were below predicted noise levels – compliant.
29/05/2025	5:13	Ventilation fans	Claremont Meadows Shaft Facility	2 Putland Street, Claremont Meadows	36	43	52	76	53.1	48	9	Yes	Ventilation fans were at no point audible during monitoring. Cars on Great Western Highway were the most dominant noise source, followed by Gipps Street, and potentially M4 traffic.
29/05/2025	5:46	Ventilation fans	Claremont Meadows Shaft Facility	4 Dolphin Close, Claremont Meadows	36	42	52.5	76.1	54	49.4	10.5	Yes	Ventilation fans were at no point audible during monitoring. Cars on Gipps St, Great Western Highway, and likely M4 highway were consistently the dominant noise source.

Appendix C Discharge to water


TABLE 8 WATER DISCHARGE TABLE

Discharge Monitoring Point ID	Type of Monitoring Point	Type of Discharge Point	Date	Discharge Permit No.	Oil and Grease (Visual inspection)	pH (6.5 - 8.5)	Turbidity (50 NTU)
SSTOM-001	Sediment basin	Discharge into stabilised spillway	1/05/2025	PMJV-ENV-DWP-93	Not visible	7.42	11
SSTOM-014	Sediment basin	Discharge into stabilised spillway	9/05/2025	PMJV-ENV-DWP-96	Not visible	7.85	12.2
SSTOM-014	Sediment basin	Discharge into stabilised spillway	29/05/2025	PMJV-ENV-DWP-98	Not visible	8.47	6.3
SSTOM-001	Sediment basin	Discharge into stabilised spillway	30/05/2025	PMJV-ENV-DWP-99	Not visible	7.42	12.5

Appendix D Surface water monitoring

No surface water monitoring was conducted for this month's monitoring report. Any surface water monitoring conducted as part of Parklife Metro's EPL licence will be presented accordingly.

Appendix E Premise Maps - May



LEGEND		Site Access Schedule	
Discharge Points	EPL Premise Boundary	Metro alignment	Temporary Area
Water Treatment Plant	Surface works	Watercourse	
	Sub-surface works	Western Sydney International boundary (WSP)	
		Aerial Stratum	
		Project Site	
		Substratum	

TITLE
EPL 21807 PREMISE BOUNDARY

NOTES	
EPL Premise Boundary Map	


PROJECT	CLIENT
Sydney Metro – Western Sydney Airport - SSTOM	Sydney Metro

SCALE	A3	DRAWN BY
1:2,000	DD	

SHEET	COORDINATE SYSTEM	REVIEW
1 of 12	GDA2020 MGA Zone 56	JB

REV	DATE	DESCRIPTION
32	26.02.2025	Premise Map update
33	05.03.2025	Premise Map update
34	28.03.2025	Premise Map update
35	01.04.2025	Premise Map update
36	05.04.2025	Premise Map update
37	20.05.2025	Premise Map update

APPROVED	MAP #	REV
JB	SMWSASSM-PLD-1NL-ENV-GIS-000001_37	37



LEGEND

EPL Premise Boundary

Surface works

Sub-surface works

Metro alignment

Watercourse

Western Sydney International boundary (WSP)

Site Access Schedule

Project Site

Substratum

Temporary Area



TITLE
EPL 21807 PREMISE BOUNDARY

PROJECT
Sydney Metro – Western Sydney Airport - SSTOM

SCALE
1:7,500


SHEET
2 of 12

COORDINATE SYSTEM
GDA2020 MGA Zone 56


0 140 280m

REV	DATE	DESCRIPTION
32	26.02.2025	Premise Map update
33	05.03.2025	Premise Map update
34	28.03.2025	Premise Map update
35	01.04.2025	Premise Map update
36	05.04.2025	Premise Map update
37	20.05.2025	Premise Map update

CLIENT Sydney Metro	APPROVED JB	MAP # SMWSASSM-PLD-1NL-ENV-GIS-000001_37	REV 37
DRAWN BY DD	REVIEW JB	DATE 20/05/2025	




LEGEND		
EPL Premise Boundary	Metro alignment	Site Access Schedule
Surface works	Watercourse	Project Site
Sub-surface works	Western Sydney International boundary (WSP)	Substratum
		Temporary Area



NOTES		REV		DATE	DESCRIPTION
EPL Premise Boundary Map		32	26.02.2025	Premise Map update	
		33	05.03.2025	Premise Map update	
		34	28.03.2025	Premise Map update	
		35	01.04.2025	Premise Map update	
		36	05.04.2025	Premise Map update	
		37	20.05.2025	Premise Map update	

TITLE EPL 21807 PREMISE BOUNDARY	PROJECT Sydney Metro – Western Sydney Airport - SSTOM	CLIENT Sydney Metro
SCALE 1:2,000	A3	DRAWN BY DD
SHEET 3 of 12	COORDINATE SYSTEM GDA2020 MGA Zone 56	APPROVED JB
	REVIEW JB	MAP # SMWSASSM-PLD-1NL-ENV-GIS-000001_37
	DATE 20/05/2025	REV 37



LEGEND			
Discharge Points	EPL Premise Boundary	Metro alignment	Site Access Schedule
Temporary Sediment Basin	Surface works	Watercourse	Project Site
	Sub-surface works	Western Sydney International boundary (WSP)	Substratum
			Temporary Area


TITLE
EPL 21807 PREMISE BOUNDARY

NOTES	
EPL Premise Boundary Map	

PROJECT Sydney Metro – Western Sydney Airport - SSTOM	CLIENT Sydney Metro
SCALE 1:5,000	APPROVED JB
SHEET 4 of 12	DATE 20/05/2025
COORDINATE SYSTEM GDA2020 MGA Zone 56	MAP # SMWSASSM-PLD-1NL-ENV-GIS-000001_37

REV	DATE	DESCRIPTION
32	26.02.2025	Premise Map update
33	05.03.2025	Premise Map update
34	28.03.2025	Premise Map update
35	01.04.2025	Premise Map update
36	05.04.2025	Premise Map update
37	20.05.2025	Premise Map update

DRAWN BY DD	REVIEW JB	MAP # SMWSASSM-PLD-1NL-ENV-GIS-000001_37	REV 37
----------------	--------------	---------------------------------------------	-----------



LEGEND		EPL Premise Boundary		Site Access Schedule	
Discharge Points	Temporary Sediment Basin	Surface works	Sub-surface works	Project Site	Temporary Area
Metro alignment	Watercourse	Western Sydney International boundary (WSP)			



TITLE
EPL 21807 PREMISE BOUNDARY


SCALE
1:5,000

SHEET
5 of 12

0 100 200m

NOTES		CLIENT	
EPL Premise Boundary Map		Sydney Metro	
REV	DATE	DESCRIPTION	
32	26.02.2025	Premise Map update	
33	05.03.2025	Premise Map update	
34	28.03.2025	Premise Map update	
35	01.04.2025	Premise Map update	
36	05.04.2025	Premise Map update	
37	20.05.2025	Premise Map update	

PROJECT		CLIENT	
Sydney Metro - Western Sydney Airport - SSTM		Sydney Metro	
SCALE	A3	DRAWN BY	MAP #
1:5,000	DD	JB	SMWSASSM-PLD-1NL-ENV-GIS-000001_37
DATE	REVIEW	DATE	REV
20/05/2025	JB	20/05/2025	37




LEGEND

- EPL Premise Boundary
- Surface works
- Sub-surface works

- Metro alignment
- Watercourse
- Western Sydney International boundary (WSP)

- Site Access Schedule
- Aerial Stratum
- Project Site
- Temporary Area



NOTES

EPL Premise Boundary Map

REV	DATE	DESCRIPTION
32	26.02.2025	Premise Map update
33	05.03.2025	Premise Map update
34	28.03.2025	Premise Map update
35	01.04.2025	Premise Map update
36	05.04.2025	Premise Map update
37	20.05.2025	Premise Map update

TITLE
EPL 21807 PREMISE BOUNDARY

PROJECT
Sydney Metro – Western Sydney Airport - SSTM

CLIENT
Sydney Metro

SCALE
1:5,000

A3

DRAWN BY
DD

APPROVED
JB

MAP #
SMWSASSM-PLD-1NL-
ENV-GIS-000001_37


SHEET
6 of 12

COORDINATE SYSTEM
GDA2020 MGA Zone 56

REVIEW
JB

DATE
20/05/2025

REV
37



LEGEND		
EPL Premise Boundary	Metro alignment	Site Access Schedule
Surface works	Watercourse	Aerial Stratum
Sub-surface works	Western Sydney International boundary (WSP)	Project Site
		Temporary Area

TITLE
EPL 21807 PREMISE BOUNDARY


NOTES	
EPL Premise Boundary Map	

PROJECT	CLIENT
Sydney Metro – Western Sydney Airport - SSTM	Sydney Metro

SCALE	A3	DRAWN BY	APPROVED	MAP #	REV
1:5,000		DD	JB	SMWSASSM-PLD-1NL-ENV-GIS-000001_37	37

SHEET	COORDINATE SYSTEM	REVIEW	DATE
7 of 12	GDA2020 MGA Zone 56	JB	20/05/2025

REV	DATE	DESCRIPTION
32	26.02.2025	Premise Map update
33	05.03.2025	Premise Map update
34	28.03.2025	Premise Map update
35	01.04.2025	Premise Map update
36	05.04.2025	Premise Map update
37	20.05.2025	Premise Map update




LEGEND

- | | | | |
|------------------------------------------------------------------------------------------------------------------------------------------------|--------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|-------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|
| <p>Discharge Points</p> <ul style="list-style-type: none"> ● Temporary Sediment Basin | <p>EPL Premise Boundary</p> <ul style="list-style-type: none"> Surface works Sub-surface works | <p>Metro alignment</p> <ul style="list-style-type: none"> Metro alignment Watercourse Western Sydney International boundary (WSP) | <p>Site Access Schedule</p> <ul style="list-style-type: none"> Aerial Stratum Project Site Temporary Area |
|------------------------------------------------------------------------------------------------------------------------------------------------|--------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|-------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|



TITLE
EPL 21807 PREMISE BOUNDARY



NOTES

EPL Premise Boundary Map

PROJECT
Sydney Metro – Western Sydney Airport - SSTM


SCALE
1:5,000

COORDINATE SYSTEM
GDA2020 MGA Zone 56

SHEET
8 of 12

REV	DATE	DESCRIPTION
32	26.02.2025	Premise Map update
33	05.03.2025	Premise Map update
34	28.03.2025	Premise Map update
35	01.04.2025	Premise Map update
36	05.04.2025	Premise Map update
37	20.05.2025	Premise Map update

CLIENT Sydney Metro	APPROVED JB	MAP # SMWSASSM-PLD-1NL- ENV-GIS-000001_37	REV 37
------------------------	----------------	-------------------------------------------------	-----------




LEGEND

- EPL Premise Boundary
- Surface works
- Sub-surface works

- Metro alignment
- Watercourse
- Western Sydney International boundary (WSP)

- Site Access Schedule
- Aerial Stratum
- Project Site
- Substratum
- Temporary Area



NOTES
EPL Premise Boundary Map

TITLE
EPL 21807 PREMISE BOUNDARY

PROJECT
Sydney Metro – Western Sydney Airport - SSTOM

SCALE
1:5,000

SHEET
9 of 12

COORDINATE SYSTEM
GDA2020 MGA Zone 56

REV	DATE	DESCRIPTION
32	26.02.2025	Premise Map update
33	05.03.2025	Premise Map update
34	28.03.2025	Premise Map update
35	01.04.2025	Premise Map update
36	05.04.2025	Premise Map update
37	20.05.2025	Premise Map update

CLIENT
Sydney Metro


APPROVED
JB

DATE
20/05/2025

MAP #
SMWSASSM-PLD-1NL-ENV-GIS-000001_37

REVIEW
JB

37



LEGEND		
EPL Premise Boundary	Metro alignment	Site Access Schedule
Surface works	Watercourse	Project Site
Sub-surface works	Western Sydney International boundary (WSP)	Temporary Area



TITLE
EPL 21807 PREMISE BOUNDARY

SCALE
1:5,000

SHEET
10 of 12

COORDINATE SYSTEM
GDA2020 MGA Zone 56

0 100 200m

NOTES
EPL Premise Boundary Map

PROJECT
Sydney Metro – Western Sydney Airport - SSTOM

SCALE
1:5,000

SHEET
10 of 12

COORDINATE SYSTEM
GDA2020 MGA Zone 56

REV	DATE	DESCRIPTION
32	26.02.2025	Premise Map update
33	05.03.2025	Premise Map update
34	28.03.2025	Premise Map update
35	01.04.2025	Premise Map update
36	05.04.2025	Premise Map update
37	20.05.2025	Premise Map update

CLIENT Sydney Metro	APPROVED JB	MAP # SMWSASSM-PLD-1NL- ENV-GIS-000001_37	REV 37
------------------------	----------------	-------------------------------------------------	-----------



LEGEND		
EPL Premise Boundary	Metro alignment	Project Site
Surface works	Watercourse	Substratum
Sub-surface works	Western Sydney International boundary (WSP)	Temporary Area
	Site Access Schedule	


TITLE
EPL 21807 PREMISE BOUNDARY

NOTES	
EPL Premise Boundary Map	

PROJECT Sydney Metro – Western Sydney Airport - SSTOM	CLIENT Sydney Metro
SCALE 1:5,000	A3
SHEET 11 of 12	COORDINATE SYSTEM GDA2020 MGA Zone 56

REV	DATE	DESCRIPTION
32	26.02.2025	Premise Map update
33	05.03.2025	Premise Map update
34	28.03.2025	Premise Map update
35	01.04.2025	Premise Map update
36	05.04.2025	Premise Map update
37	20.05.2025	Premise Map update

APPROVED JB	MAP # SMWSASSM-PLD-1NL- ENV-GIS-000001_37	REV 37
DATE 20/05/2025		



LEGEND			
Discharge Points	EPL Premise Boundary	Metro alignment	Site Access Schedule
● Temporary Sediment Basin	▭ Surface works	— Watercourse	▭ Project Site
● Water Treatment Plant	▭ Sub-surface works	▭ Western Sydney International boundary (WSP)	▭ Substratum
			▭ Temporary Area

Parklife Metro D&C

TITLE: EPL 21807 PREMISE BOUNDARY

SCALE: 1:5,000

0 100 200m

NOTES	
EPL Premise Boundary Map	

PROJECT	CLIENT
Sydney Metro – Western Sydney Airport - SSTM	Sydney Metro

SCALE	A3	DRAWN BY	APPROVED	MAP #
1:5,000		DD	JB	SMWSASSM-PLD-1NL-ENV-GIS-000001_37

SHEET	COORDINATE SYSTEM	REVIEW	DATE
12 of 12	GDA2020 MGA Zone 56	JB	20/05/2025

REV	DATE	DESCRIPTION
32	26.02.2025	Premise Map update
33	05.03.2025	Premise Map update
34	28.03.2025	Premise Map update
35	01.04.2025	Premise Map update
36	05.04.2025	Premise Map update
37	20.05.2025	Premise Map update